

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 110-11

LOCATION CNW NE

SEC. 15 TWP. 15 RGE. 39

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease ~~XXXXXX~~ Frasier Frasier ~~XXXXXX~~

Operator Van-Grisso Oil Co Address 1012 City Natl Bldg Oklahoma City

Field \_\_\_\_\_ County Wallace

Total Depth 5260 Feet.

Plugging Contractor Messman & Rinehart & R & D Pipe Pulling Co

Plugging Contractor's License No. R&D 236

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

13" at 245' circulated with cement - 8 5/8" at 2715' with 200  
sax cement behind - Messman & Rinehart Drg co circulated hole  
with heavy mud, set cementing plug at 2500', displaced 25 sax cement  
through drill pipe - R & D Casing pulling pulled 1180' 8 5/8" -  
mudded hole to 240', set rock and 30 sax cement, heavy mud to  
20', set rock and 15 sax cement to bottom cellar.

PLUGGING  
FILE SEC 15 T. 15 R. 39W  
BOOK PAGE 110 LINE 11

Edson Peck  
District Conservation Agent

Date 11-12-56 11-24-56