

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bradley-Shaw,

Complete Address: 826 Union Center Building, Wichita, Kansas.

Lease Name Pearce Well No. 1

Location CNE-SE Sec. 2 Twp. 14 Rge. (E) (W)1

County Wallace Total Depth 5320'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Rine Drilling Company, Incorporated,

Address: 420 Union Center Building, Wichita, Ks. License No.

Operation Completed: Hour 6:00AM Day 31 Month 1 Year 1969

The Above well was plugged as follows:

367'--8 5/8" Surface casing, cement circulated with 275 Sx.
12 1/4" Hole drilled to 445'. Surface casing had parted @ 294'. Electric log showed
no sand section.

Circulated hole with heavy mud. Pulled DP to 420' and displaced 80 Sx. cement thru
DP from 420' to 180'. Pulled DP, set bridge @ 45' with 1/2 sack hulls and 20 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INDEXED
DATE 2/3/69
INV. NO. 9272-u