

KANSAS

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Comet Petroleum Corporation,

Complete Address 608 Union Center Building, Wichita, Kansas.

Lease Name Clark-Mobil Well No. #1

Location CNE-NE Sec. 27 Twp. 15 Rge. (E) (W) 11

County Wallace Total Depth 5517'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 PM Day 7 Month 1 Year 1970

The above well was plugged as follows:

631'--8 5/8" Surface casing, cement circulated with 350 Sx.
Top of Dakota section @ 1600'.

Circulated hole with heavy mud. Pulled DP to 1825' and displaced 100 Sx. cement thru
DP from 1825' to 1500'. Pulled DP to 650' and displaced 25 Sx. cement thru DP from
650' to 575'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1/12/70
INV. NO. 1234-W