

15-199-2000 4. 00-00

Form CP-3
Rev. 6-4-68

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
DEC 8 1969
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
12-08-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Trend Exploration, Limited,
Complete Address 600 Capital Life Center, Denver, Colorado. 80203
Lease Name R. Waugh Well No. 1
Location CNE-SW Sec. 16 Twp. 14 Rge. (E) (W) 42
County Wallace Total Depth 5600'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones, Incorporated,
Address 830 Sutton Place, Wichita, Kansas. License No.
Operation Completed: Hour 3:30 AM Day 3 Month 12 Year 1969

The above well was plugged as follows:

324'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ ~~324'~~ 1600'.
Circulated hole with heavy mud. Pulled DP to 1825' and displaced 100 Sx. cement thru
DP from 1825' to 1500'. Pulled DP to 425' and displaced 40 Sx. cement thru DP from
425' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 12/9/69
INV. NO. 1001-W

Signed: *W. L. Nichols*
Well Plugging Supervisor