

15-671-20017-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dorchester Exploration Company,

Complete Address 1204 Vaughn Building, Midland, Texas.

Lease Name Wear Well No. 1

Location CSE Sec. 23 Twp. 17 Rge. (E) (W) 40

County Greeley Total Depth 3006'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sterling Drilling Company,

Address Box #129, Sterling, Kansas. License No.

Operation Completed: Hour 12:00 PM Day 1 Month 21 Year 1973

The above well was plugged as follows:

378'--10 3/4" Surface casing, cement circulated with 300 Sx. (9" Hole to 1840').

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 140 Cu. Ft. cement

thru DP from 1350' to 1035'. Pulled DP to 400' and displaced 40 Cu. Ft. cement thru

DP from 400' to 325'. Pulled DP, set bridge 0 40' with 1/2 sack hulls and 20 Cu. Ft.

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 1/24/73
INV. NO. 6900-W