

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21059-00-00
Spot: NESESSEW Sec/Twnshp/Rge: 34-32S-18W
1003 feet from S Section Line, 2775 feet from E Section Line
Lease Name: DALE Well #: 3
County: COMANCHE Total Vertical Depth: 5275 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: 414 PLAZA DR STE 204
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5008		WITH 4 SX CMT
SURF	8.625	679		WITH 375 SX CMT
COND	20	70		WITH 7 SX CMT
PROD	4.5	5275	4080	WITH 180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/08/2011 8:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION Phone: (620) 786-9166

Proposed Plugging Method: SET CIBP @ 5008' WITH 4 SX CMT. PLUG AT 1030' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 09/08/2011 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5008' WITH 4 SX CMT. 1ST PLUG AT 1030' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5058			


RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SARGENT LILLARD

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED

SEP 16 2011

KCC DODGE CITY

Form CP-208

9/29/11