

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20339-00-00  
Spot: SWSWNEW Sec/Twnshp/Rge: 1-32S-33W  
4070 feet from S Section Line, 3850 feet from E Section Line  
Lease Name: NORTHERN NATURAL Well #: 1  
County: SEWARD Total Vertical Depth: 2756 feet

Operator License No.: 33988  
Op Name: LEBOSQUET GAS OPERATIONS, LLC  
Address: 535 S EMPORIA STE 103  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 1960       |             |                 |
| SURF   | 8.625 | 733        |             | WITH 250 SX CMT |
| PROD   | 4.5   | 2754       | 0           | WITH 250 SX CMT |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2011 1:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: RIHWT TO 1950' & PUMP 40 SX CMT. PERFORATE @ 750' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 09/09/2011 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

EST. TOC 1754'. 1ST PLUG RIHWT TO 1952'. MIX & PUMP 100# HULLS & 60 SX CMT. TAG TOC @ 1420'. 2ND PLUG PERFORATE CASING @ 733'. MIX & PUMP 145 SX CMT. EST. 100 SX CMT OUTSIDE CASING. 3RD PLUG HOOK UP 8 5/8" X 4 1/2" ANNULUS. PUMP 25 SX CMT. SHUT IN WITH 600#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2668 | 2678 |      |          |

RECEIVED  
SEP 23 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED  
SEP 16 2011  
KCC DODGE CITY

Form CP-2/3

9/29/11