

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-20940-00-00
Spot: N2NENESE Sec/Twnshp/Rge: 9-24S-10E
2640 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHWAB Well #: 4
County: GREENWOOD Total Vertical Depth: 2840 feet

Operator License No.: 31772
Op Name: BLACK STAR 231 CORP.
Address: LIVESTOCK EXCHANGE BLDG 1600
KANSAS CITY, MO 64102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	65		60 SX
PROD	5.5	2824		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2011 8:00 AM
Plug Co. License No.: 32147 Plug Co. Name: K.E. SNYDER CO., LLC
Proposal Rcvd. from: JIM SNYDER Company: _____ Phone: (620) 344-6283

Proposed Plugging Method: MIXED AND CIRCULATE MUD IN WELL. SPOT THROUGH TUBING PLUGS @ 2840, 2,000, 1,200, 100' TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 09/13/2011 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

RAN TUBING TO 2813" PUMPED 30 SXS CEMENT, PULLED TUBING TO 900'
PUMPED 20 SXS CEMENT, PULLED TUBING TO 150' CIRC. CEMENT TO SURFACE,
37 SXS CEMENT, GEL SPACERS BETWEEN CEMENT PLUGS, SHOT CASING @ 900'
& 150'

Perfs:

RECEIVED

SEP 19 2011 MH

KCC Chanute Dist. #3

RECEIVED
SEP 27 2011

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

Form CP-2/3

9/29/11