

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21218-00-00  
Spot: NENESENV Sec/Twnshp/Rge: 34-32S-18W  
1540 feet from N Section Line, 2383 feet from W Section Line  
Lease Name: DALE Well #: 4  
County: COMANCHE Total Vertical Depth: 5806 feet

Operator License No.: 5254  
Op Name: MIDCO EXPLORATION, INC.  
Address: 414 PLAZA DR STE 204  
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4682		WITH 2 SX CMT
CIBP		5131		
SURF	8.625	722		316 SX
COND	20	78		WITH 8 SX CMT
PROD	4.5	5746	4008	250 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2011 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: DAVID MAYFIELD Company: MIDCO EXPLORATION Phone: (620) 786-9166

Proposed Plugging Method: SET CIBP @ 4682' WITH 2 SX CMT. PLUG AT 1030' WITH 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2011 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4682' WITH 2 SX CMT. CIRCULATED GEL. 1ST PLUG AT 1030' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5664	5669		
5136	5141		
4955	4957		
4732	4734		

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

RECEIVED  
SEP 21 2011  
KCC DODGE CITY

Signed

*Eric MacLaren*

(TECHNICIAN)

RECEIVED  
SEP 29 2011 Form CP-2/3  
KCC WICHITA