

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20092-00-00  
Spot: SW Sec/Twnshp/Rge: 11-28S-33W  
1320 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: GUTTRIDGE Well #: 1  
County: HASKELL Total Vertical Depth: 2740 feet

Operator License No.: 33988  
Op Name: LEBOSQUET GAS OPERATIONS, LLC  
Address: 535 S EMPORIA STE 103  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		748		
SURF	8.625	703		WITH 400 SX CMT
PROD	5.5	2740	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2011 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: 1ST: SET CIBP AT 2600' + 2 SXS CEMENT OR RIHWT TO 2600', PUMP 200# HULLS + 25 SXS CEMENT. 2ND: PULL TUBING TO 1710', PUMP 25 SXS CEMENT WITH 100# HULLS. 3RD: PERFORATE 5-1/2" CASING AT 720' AND CIRCULATE CEMENT TO SURFACE (60/40 POZ MIX W/ 4% GILSONITE).

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/08/2011 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

9/7/11: 1ST PLUG RIHWT PUMP 35 SX CMT & 100# HULLS. NO CIRCULATION. 2ND PLUG PULL TBG TO 1707'. PUMP 50 SX CMT & 150# HULLS. GOOD CIRCULATION. 3RD PLUG TAG TOC @ 1222. TEST CASING. FAILED. SET CIBP @ 748'. TEST CASING. SLIGHT LEAK. BLOW ON ANNULUS. 4TH PLUG PERFORATE CASING AT 720'. RATE 3.5 BPM @ 0 PSI. CIRCULATE CMT TO SURFACE WITH 190 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2692	2700		
2686	2692		
2669	2675		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
SEP 21 2011  
KCC DODGE CITY

RECEIVED

SEP 29 2011 9/29/11

KCC WICHITA