

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25282-00-00
Spot: NWSENE Sec/Twnshp/Rge: 28-18S-21W
840 feet from N Section Line, 430 feet from E Section Line
Lease Name: RYERSEE Well #: 3-28
County: NESS Total Vertical Depth: 4194 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1345		WITH 425 SX CMT

Well Type: DH UIC Docket No: Date/Time to Plug: 08/17/2011 8:50 AM
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC
Proposal Revd. from: KENNY ROACH Company: PETROMARK DRILLING, LLC Phone: (316) 734-8977

Proposed Plugging Method: IST PLUG AT 1370' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 08/17/2011 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

IST PLUG AT 1370' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: DP

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
SEP 21 2011
KCC DODGE CITY

RECEIVED
SEP 29 2011
KCC WICHITA