

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23034-00-02
Spot: NWSWSW Sec/Twnshp/Rge: 1-21S-11W
987 feet from S Section Line, 345 feet from W Section Line
Lease Name: YATES A OWWO Well #: 1-1
County: STAFFORD Total Vertical Depth: 3500 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3420		
CIBP		3475		
SURF	8.625	268		WITH 225 SX CMT
PROD	4.5	3496	1435	WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2011 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3340' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2011 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3332' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 608' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 281' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3420			
3395	3397		ARBUCKLE
3290	3298		

Remarks: USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY WELL SERVICE. **THE CALCIUM CHLORIDE WAS NOT REQUESTED**

Plugged through: CSG

District: 01

RECEIVED

SEP 21 2011

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

OCT 03 2011

KCC WICHITA

Form CP-2/3