

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21018-00-00
Spot: NENWSW Sec/Twnshp/Rge: 19-12S-37W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: WRIGHT Well #: 12A-19-1237
County: LOGAN Total Vertical Depth: 4900 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	470		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/21/2011 12:00 AM
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC
Proposal Revd. from: GARY Company: FIML NATURAL RESOURCES, LLC Phone: (303) 893-5073

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN Witness Type: NONE
Date/Time Plugging Completed: 09/21/2011 9:15 AM KCC Agent: DAVID WANN

Actual Plugging Report:

1st. Plug at 2500' w/25 sxs.
2nd. Plug at 1630' w/100 sxs.
3rd. Plug at 520' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED Form CP-2/3

OCT 03 2011

SEP 21 2011

KCC WICHITA