

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 4058 Name: American Warrior Inc. Address 1: P.O. Box 399 Address 2: City: Garden City State: Ks Zip: 67846 Contact Person: Jody Smith Phone: (620) 275-2963 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) NA Depth to Top: 4083' Bottom: 4085 T.D. 4600'

API No. 15 - 047-20514 -00-00 Spot Description: SW NW NE Sec. 5 Twp. 25 S. R. 17 East West 4,296 Feet from North South Line of Section 2,275 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Edwards Lease Name: Mundhenke Well #: 1-5 Date Well Completed: 3/20/80 The plugging proposal was approved on: 9/14/11 by: Steve Pfeifer (KCC District Agent's Name) Plugging Commenced: 9/26/11 Plugging Completed: 9/26/11

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: NA, Gas, surface, 85/8, 600', 0. Row 2: NA, Gas, Production, 4 1/2, 4606', 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4000'w/2 sx cement. Perf 1100' to 1101', Ran tbg to 1100'. Swift hooked up to tbg, Mixed and pumped 385sx 60/40 poz, 4% gel cement. Circulated cement out 4 1/2 Annulus and shut in, Circulated cement out 85/8 and shut in. Pulled tbg. Topped 4 1/2 off with 15sx. Cut casing off 6' below surface and backfilled.

Plugging Contractor License #: 32382 Name: Swift Services, Inc. Address 1: P.O. Box 466 Address 2: City: Ness City State: Ks Zip: 67560 + 0466 Phone: (785) 798-2300 Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss. Jody Smith (Print Name) Employee of Operator or Operator on above-described well, [checked]

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Handwritten Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED SEP 30 2011

KCC WICHITA