


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Saline County. Sec. 31 Twp. 15 Rge. 1 W E/W  
Location as "NE/CNW/SW" or footage from lines  
SE NE NE

Lease Owner George Hess  
Lease Name Hess Well No. 4  
Office Address P.O.Box 89 McPherson, Kansas 67460  
Character of Well (Completed as Oil, Gas or Dry Hole) oil



Locate well correctly on above  
Section Plat

Date Well completed 12-30 1969  
Application for plugging filed 8-17 1978  
Application for plugging approved 8-18 1978  
Plugging commenced 10-24 1978  
Plugging completed 10-27 1978  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production  
19 \_\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2704'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2518'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Plugged off bottom of hole with sand. Sand from 2704' to 2650'. Dumped 5 sx of cement. Mudded hole to 150'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 30 1978  
10-30-78

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Inc.  
2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1978

My commission expires April 18, 1982

Judy Lamb  
Notary Public.

## DRILLERS LOG

Company	George R. Hess	Commenced 12/23/69
Contractor	Slusser Drilling Company	Completed 12/30/69
Farm	Hess #4	SE NE NE 31-15-1W
8 5/8	@ 138	Saline Co., Kansas
4 1/2	@ 2697	
Elevation 1303 Derrick Floor		

Surface soil	5
Sand and shale	50
Shale	100
Lime and shale	150
Shale and lime	460
Lime and shale	720
Shale and shells	1595
Lime and shale	1965
Shale and lime	2067
Lime	2475
Lime and shale	2685
Chat	2704 Rotary T.D.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 18 1978

CONSERVATION DIVISION  
Wichita, Kansas