

15.169.00053.0001


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 31 Twp. 15 Rge. 1W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW NE NE
Lease Owner George Hess
Lease Name George Hess Well No. 1
Office Address MC Pherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole.
Date well completed Aug 25 1958
Application for plugging filed March 1963
Application for plugging approved March 1963
Plugging commenced March 27 1963
Plugging completed March 29 1963
Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2770' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/8"		2,511'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 2,770' to 2,695'. Dumped 5 sx of cement. Mudded hole to 165'. Made 10' of rock bridge. Dumped 20 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1963

4-8-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address P.O. Box 983 Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 Kings Dr. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1963.

My commission expires January 5, 1966

Judy Lamb
Notary Public.

4/8/63
NO. 6858-W

my farm

COMPANY: George Hess
CONTRACTOR: Mallard Drilling Company
FARM: George Hess #1
LOCATION: NW 1/4 Sec. 31-15-1W
 Saline County, Kansas
COMMENCED: August 15, 1958
COMPLETED: August 25, 1958

0	to	75	Shale and sand
75	to	166	Shale
166	to	380	Lime
380	to	765	Lime
765	to	1580	Shale and lime
1580	to	2077	Shale and lime
2077	to	2095	Lime
2095	to	2435	Lime
2435	to	2725	Lime and shale
2725	to	2770	Mississippi
		2770	T.D. Rotary

RECEIVED
 STATE CORPORATION COMMISSION
 APR 8 1963
 CONSERVATION DIVISION
 Wichita, Kansas

Set 166 feet of 8 5/8" surface pipe. Cemented with 100 sacks cement.

TOPS: Brown line --- 2014 Kansas City --- 2077 Top chat-- 2704
 Elevation-- 1930

DEEP, ABANDONED AND PLUGGED

MISSOURI PROPERTY

CERTIFICATE

I, C. G. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the George Hess #1, Saline County, Kansas, as reflected by files of the Mallard Drilling Company.

C. G. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgewick County, Kansas, this 13th day of September 1958.

My commission expires March 12, 1962

Geo. H. Sear
 D.S.T. top of lime here 15 ft
 heavy mud few spots of sand
 hole out B.A.P. 1990 and
 still increasing
 Lime was 100%
 soluble in acids
 8-1758 Geo. H. Sear