


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 33 Twp. 15 Rge. 1 (E) 1 (W)
Location as "NE/CNW/SE" or footage from lines S/2 SE NW

Lease Owner Cal Jones

Lease Name Tinkler-Everhart Well No. 1

Office Address Canton, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed Dec. 10 19 65

Application for plugging filed " 19 65

Application for plugging approved " 19 65

Plugging commenced " 19 65

Plugging completed " 19 65

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2642 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	132'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

heavy mud 2642 to 125'

wooden plug & 1/2" x hulls @ 125'

20sx cement on plug

heavy mud to 40'

plug as above @ 40'

surface soil to 0'

RECEIVED
STATE CORPORATION COMMISSION
12-30-65
DEC 30 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Melland Drilling Co., Inc.
Address Box 783 McPherson, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Donald J. Melland (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald J. Melland
Box 783 McPherson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 65

My commission expires December 23, 1967

[Signature]
Notary Public.

WELL RECORD

LEASE: Pinkler-Everhart

WELL NO. 1

ELEVATION:

LOCATION: 3/2 SE NW
Sec. 33-25-1W

COMMENCED: 12/5/65

COMPLETED: 12/10/65

OPERATOR: Gal Jones

CONTRACTOR: Melland Drilling Company, Inc.
Post Office Box 783
McPherson, Kansas

CASING RECORD: 8 5/8" @ 132'/90sx

FORMATION	LOG
sandy shale	50
anhydrite	132
anhydrite	193
lime	769
lime & shale	789
shale & shells	1290
shale	1554
shale & lime	1762
shale & sand	1968
lime & shale	2314
shale & shells	2639
Mississippi	2642
RTD	2642
Sample Tops	
Lansing	1968
Mississippian	2633

FORMATION LOG

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1965

CONSERVATION DIVISION
WELL SERVICES

CERTIFICATE

State of Kansas, County of McPherson, ss.

I, Donald J. Melland, do hereby certify that the above is a true and correct copy of the log of the above-named and described well, as reflected by the records of the Melland Drilling Company, Inc.

Donald J. Melland

Subscribed and sworn to before me, a Notary Public, in and for the County of McPherson, State of Kansas, this 13th day of December, 1965.

My Commission expires: December 23, 1967

James P. Melland
_____ Notary Public