


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 32 Twp. 15 Rge. 1W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE NE SW
Lease Owner Clifton L. McCown
Lease Name Mc Lin Well No. 1
Office Address Union Nat'l. Bank - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 25 19 53
Application for plugging filed April 13 19 53
Application for plugging approved April 15 19 53
Plugging commenced April 17 19 53
Plugging completed April 21 19 53
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
None				5-1/2"	2718'	2420'
				8-5/8"	130'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 2718' to 2675' and ran 6 sacks of cement. Mud filled to 130'. Set rock bridge from 130' to 120' and ran 15 sacks of cement. Mudded hole to 30', set rock bridge to 18' and ran 5 sacks of cement. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1953
5-19-53
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clifton L. McCown (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clifton L. McCown
531 Petroleum Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May 19 53
Wilma Whitmer
Notary Public.

My commission expires 2/11/57
PLUGGING
FILE SEC 32 T 15 R 1W
BOOK PAGE 98 LINE 45

COMPANY: Clifton Mc Cown
 CONTRACTOR: Mellard Drilling Company
 FARM: Mc Lin #1
 LOCATION: NE NE SW Sec. 32-15-1
 Saline County, Kansas
 COMMENCED: March 17, 1953
 COMPLETED: March 25, 1953

0	to	130	Shale
130	to	240	Lime
240	to	615	Lime
615	to	860	Lime and sand
860	to	1615	Lime and shale
1615	to	1740	Lime
1740	to	2005	Sand and shale
2005	to	2024	Shale
2024	to	2105	Lime
2105	to	2310	Lime
2310	to	2415	Lime and shale
2415	to	2530	Lime and shale
2530	to	2679	Shale and lime
2679	to	2686	Mississippi
2686	to	2718	Lime and chert
		2718	T. D. Rotary

2679

Set 130' of 8 5/8" surface pipe. Cemented with 90 sacks cement.

Set 5 1/2" at 2718. Cemented with 50 sacks cement.

TOPS: 2651-- Mississippi

Measurements taken from derrick floor.

RECEIVED
 STATE COLLOCATION COMMISSION
 APR 14 1953
 CONSERVATION DIVISION
 Wichita, Kansas

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Mc Lin #1, Saline County, Kansas, as reflected by filed of the Mellard Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Sedgewick County, Kansas, this 30th day of March 1953.

Raywell Wright

My commission expires

12/4/56

PLUGGING
 FILE SEC 32 T 15 R 14
 BOOK PAGE 93 LINE 25

CONSERVATION DIVISION
 Wichita, Kansas