

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Saline County, Sec. 32 Twp. 15 Rge. 1 W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner George Hess
Lease Name P. Betho Well No. I
Office Address 505 North Charles McPherson, Kansas 67460
Character of Well (completed as Oil, Gas or Dry Hole) D H
Date well completed 5-2 19 70
Application for plugging filed 6-27 19 70
Application for plugging approved 6-28 19 70
Plugging commenced 6-30 19 70
Plugging completed 7-2 19 70
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 2738' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,480'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 2738' to 2720'. Dumped 5 bx cement. Mudded hole to 140'. Made 10' of rock bridge. Dripped 30 bx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 bx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
7-6-70
JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Easing Pulling Co.
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of July, 1970

My commission expires Jan 5, 1974

[Signature] Notary Public.



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

May 4, 1970

COMPANY: GEORGE R. NESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: P. BETHE #1
 LOCATION: SW NW NW. Sec. 32-15-1W, Saline County, Kansas
 COMMENCED: April 24, 1970
 COMPLETED: May 2, 1970
 ELEVATION: 1321 K. B.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 29 1970
 CONSERVATION DIVISION
 Wichita, Kansas

0	to	130	Shale
130	to	424	Shale & Lime
424	to	729	Lime & Shale
729	to	1465	Shale & Lime
1465	to	2090	Lime & Shale
2090	to	2450	Lime
2450	to	2595	Lime & Shale
2595	to	2720	Shale & Lime
2720	to	2738	Mississippi
		2738	T. D.

Cut 12 1/4 in hole to 130 ft. and run 131.75 ft. of 8 5/8 in. surface pipe, cemented with 100 sacks at 130 ft., plug down at 11:00 A. M., April 24, 1970. Cut 7 7/8 in. hole to 2738 ft. and run 2755 ft. of 5 1/2 in. pipe, cemented with 40 sacks 8 foot off bottom at 2730 ft. Plug down at 10:30 P. M., May 2, 1970.

TOPS: BROWN LIME - 2005' LANSING - 2068' MISSISSIPPI - ~~2000~~' ²⁶⁹⁵⁻¹³⁷⁴

Measurements taken from K. B.

CERTIFICATE

I, F. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your P. Bethe #1, located on the SW NW NW, Sec. 32-15-1W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

F. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 4th day of May, 1970.

Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public

My Commission Expires: June 27, 1973.

