

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County, Sec. 32 Twp. 15 Rge. 1 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Frank J. Black

Lease Name Mason Well No. 1

Office Address McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2-13-62 19

Application for plugging filed 8-19-66 19

Application for plugging approved 8-22-66 19

Plugging commenced 8-22-66 19


Plugging completed 8-23-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

T - 15S NORTH R - 1W



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation Depth to top Bottom Total Depth of Well 2663 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	145'	None
				4-1/2"	2660'	2297'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 2663', sanded hole to 2650' and dumped 3 sacks of cement @ 2650' with dump bailer. Pulled 4 1/2" casing, set rock bridge @ 145' and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

SEP 18 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY License #436
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 1966

Milton J. Volin
Notary Public.

My commission expires May 20, 1968

WELL RECORD

15-169-00003-0000

LEASE: Mason

WELL NO. 1

LOCATION: NE/4 SE/4 NE/4
Sec. 32-15S-1W
Saline County, Kansas

COMMENCED: 2/7/62

COMPLETED: 2/13/62
(rotary)OPERATOR: Dale Reese
147 North Santa Fe
Salina, KansasCONTRACTOR: Melland Drilling Company, Inc.
1111 North Main Street
Hutchinson, KansasCASING RECORD: 8-5/8" set at 145' with 105 sacks of cement.
~~5-1/2" set at 2663' with 60 sacks of cement.~~
4 1/2"FORMATIONLOG

Surface soil & clay	25
Shale & shells	55
Anhydrite	220
Lime & shale	920
Shale & lime	1075
Shale	1490
Lime	1540
Lime & shale	1795
Sand & shale	1893
Shale	1970
Lime & shale	2624
Mississippi Lime	2663
	Total Depth

1- 10X16 Redwood Receiving TANK
NEW TANK - Used HEAD + BOTTOM1- NEW 12'X10' (3/16-10-10) welded
Steel Stock TANK.

1- Lister Diesel Air Cooled Engine

1- Parkersburg Chain Pump Unit NEW #2332.45

Casing 4 1/2"

Tubing 2"

Rods 3/4"

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1966

CONSERVATION DIVISION
Wichita, Kansas