


R

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Marion County, Sec. 32 Twp. 18 Rge. 4 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW 8E SE
Lease Owner Roland Jones
Lease Name Spachek Well No. 4
Office Address 109 S. Main, McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-17, 1960
Application for plugging filed 4-3, 1964
Application for plugging approved 4-3, 1964
Plugging commenced 4-9, 1964
Plugging completed 4-11, 1964
Reason for abandonment of well or producing formation Production Exhausted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 2-10, 1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation Mississippi, Chat Depth to top 2381 Bottom 2445 Total Depth of Well 2445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	180	None
				5 1/2	2385	2125

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 2375' with sand
Dumped 5 sacks of cement on sand
Pulled pipe
Filled hole with mud to 170'
Set bridge on mud
Dumped 20 sacks of cement on bridge
Filled with mud to 35'
Set plug on mud
Filled to surface with cement
Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slusser Drilling Company
Address Box 275, Marion, Kansas

STATE OF Kansas COUNTY OF Marion, ss.
Billy H. Slusser (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Billy H. Slusser
Box 275, Marion, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th. day of May, 1964

My commission expires July 6, 1967

Vivian I. Mott
Notary Public.

DRILLERS LOG

15-115-01603-0000 (9)

Company	Roland Jones	Commenced	6-17-60
Contractor	Siusser Drilling Company	Completed	7-1-60
Farm	Spachek #4	NW SE SE	32-18-4
8 5/8	● 180	Marion Co.,	Kansas
5 1/2	● 2385		

Surface Soil	5
Shale & Shells	150
Broken Lime	200
Lime & Shale	310
Shale & Lime	540
Shale & Shells	1165
Shale & Lime	1470
Lime & Shale	1700
Shale & Lime	1890
Lime	2145
Lime & Shale	2375
Shale	2381
Chat	2393 Rotary T. D.

Chat Soft	2393-2395	
Chat Soft	2395-2403	Show of oil
Chat Soft	2403-2410	Good show of oil; 500' of fluid in 2 hours
Chat Semi-Soft	2410-2416	
Chat	2416-2422	
Chat Firm	2422-2429	
Chat Hard	2429-2434	
Chat Firm	2434-2441	
Chat & Lime	2441-2445	Cable Tool T. D.

15-115-01603-0000

OPERATOR Roland Jones

WELL NO.

4 Spachek

ELEV. 1419 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Kc	1890				
M	2381				
RTD 2393					
CO DD 2445 FU 1.250' oil + W /12 hrs. Frac. 42 x 8					
POP					

K. G. S. LIBRARY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

COPY


Company. **ROLAND JONES**
Farm- **Spachek** No. **4**

SEC. **32** T. **18** R. **4E**
NW SW SE

15-115-01603-0000

Total Depth. **2445'**
Comm. **6-17-60** Comp. **7-1-60**
Shot or Treated.
Contractor. **Slusser Drilling Co.**
Issued. **9-10-60**

County **Marion**
KANSAS



CASING:

8 5/8" @ 180'
5 1/8" @ 2385'

Elevation. 1421.00

Production. **55 BOPD**

Figures indicate Bottom of Formations.

surface soil	5
shale & shells	150
broken lime	200
lime & shale	310
shale & lime	540
shale & shells	1165
shale & lime	1470
lime & shale	1700
shale & lime	1890
lime	2145
lime & shale	2375
shale	2381
chat	2393 RTD
chat	2395
chat - show of oil	2403
chat - good show of oil; 500' of fluid in 2 hrs.	2410
chat	2422
chat firm	2429
chat hard	2434
chat firm	2441
chat & lime	2445
Total Depth	

1421
2381
- 960

SCOUT TOPS:

Mississippi Chat 2381

K. G. S. LIBRARY