

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1972 02-11-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bowers Drlg. Co.

Complete Address 1434 Vickers KSB&T Bldg. Wichita, Ks.

Lease Name Thomas Well No. 1

Location NW/NW/NE Sec. 11 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4375

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 11:00 AM Day 9 Month 2 Year 1972

The above well was plugged as follows:

465 ft 8 5/8 /surface pipe cemented with 375 sacks. 4368 ft 4 1/2 long
string cemented with 175 sacks. Top perf. 4055 ft. Sand back to
4000 ft., 4 sacks cement with bailer. Pulled 2845 ft 4 1/2. Set 10 ft
rock bridge at 270 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: D. Russell Hunter
Well Plugging Supervisor

DATE 2/11/72
INV. NO. 5144-W