

15-119-10123-0000

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
~~212 N. MARKET~~ 212 N. MARKET  
Wichita, Kansas

FILE NO. 22-9

LOCATION CSW NE

SEC. 36 TWP. 32 RGE. 30W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 3 Lease Bachman

Operator Peerless Oil & Gas Company Address P. O. Box 245, Hooker, Okla.

Field Stevens County Meade

Total Depth 5848 Feet.

Plugging Contractor Midwestern Drillers & Halliburton

Plugging Contractor's License No. \_\_\_\_\_

Address 1206 Mid-Continent Bldg. Tulsa, Okla.

(Describe Briefly the manner in which the well was plugged)

After logging well, hole filled with heavy mud. Set cement plug with drill pipe from 5254' to 5501' which consisted of 75 sacks of common cement. Set a top plug from 1528' to 1590' with 25 sx of common cement. The top plug is near the bottom of the 9 5/8" casing. Cement pumped by Halliburton Cementers of Liberal, Ks.

Officially plugged well by welding cap on top of 9 5/8" casing 4' below ground level.

King's Welding Service, Guymon, Okla., placed cap on well on July 26, 1957.

Used 800 sx of Pozmix #1 to cement 9 5/8" casing. Cement circulated on this casing making it impossible to pull any of the casing.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1958

CONSERVATION DIVISION  
Wichita, Kansas

*R. J. Phillips*  
District Conservation Agent

Date July 26, 1957

PLUGGING  
FILE SEC. 36T 32R 30W  
BOOK PAGE 22 LINE 9