

15-051-20252-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.
Complete Address R. R. # 2 Victoria, Kansas 67671
Lease Name H. B. Mabee Windholz Well No. 1
Location SW NW SE Sec. 2 Twp. 13 Rge. (E) (W) 16
County Ellis Total Depth 3462'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling, Inc.
Address Box 1082 Great Bend, Kansas 67530 License No. 623
Operation Completed: Hour 5:15 P Day 17 Month 10 Year 1973

The above well was plugged as follows:

Total Depth 3462' 8 5/8 csg set at 143' cwc 110 sk.
4 1/2 csg set at 3450' cw 200 sk cmt.
4 1/2 csg PBD 3417' with top perf. (3232')
Filled 4 1/2 csg W/sd (3200-3417) dumped 2 sk cmt W/dump bailer. (3175-3200)
Cutoff and recovered 2062' of 4 1/2 csg.
Pumped down 8 5/8 csg with 25 sk gel & water W/200 lbs hulls -- released 8 5/8 plug
& pumped 130 sk 50-50 poz cmt W/6% total gel by Sun Cementing Co.
Max PP 300 lbs. SIP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: L. P. Draney
Well Plugging Supervisor

INVOICED

DATE 10/23/73

INV. NO. 8057-W