

15-191-20021-0090




STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 14 Twp. 35S Rge. 1E (E) XX (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner Adair & Jenkins  
Lease Name Mary Mae Well No. 1  
Office Address 905 1/2 South Main, Stillwater, Oklahoma 74074  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed May 29, 19 67  
Application for plugging filed December 30, 19 70  
Application for plugging approved December 30, 19 70  
Plugging commenced December 31, 19 70  
Plugging completed January 1, 19 71

Reason for abandonment of well or producing formation well was shut-in after completion for possible future treatment, parties decided to plug  
If a producing well is abandoned, date of last production no production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation N/A Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3619' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	none
				4 1/2"	3619'	2315'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 10 sx of cement with mud to 3000'. Shot casing at 2506', 2410', 2315'. Pulled casing up to 250' & pumped 25 sx cement for fresh water plug. Cut off surface pipe 3' below ground level & capped surface pipe with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
01-07-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John R. Martin  
Address Post Office Box 383, Cushing, Oklahoma 74023 - plugging under C. B. Smith #205 permit


STATE OF OKLAHOMA, COUNTY OF PAYNE, ss.  
WILLIAM A. JENKINS (CO-OWNER) (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William A. Jenkins

Post Office Box 906, Stillwater, Oklahoma  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 19 71

My commission expires August 12, 1973



Barbara P. [Signature]  
Notary Public.



# INDUCTION • ELECTRIC LOG

COMPANY ADAIR & JENKINS  
 WELL MARY MAE # 1  
 FIELD HEUSZEL  
 County SUMNER State KANS.

COMPANY ADAIR & JENKINS 15-191-20021-0000

WELL MARY MAE # 1

FIELD HEUSZEL

COUNTY SUMNER STATE KANSAS

Location NE NW NE

Other Services:

Sec. 14 Twp 35S Rge 1E

Permanent Datum GROUND LEVEL Elev. 1160'  
 Log Measured From KELLY BUSHING, 5 Ft. Above Perm. Datum  
 Drilling Measured From KELLY BUSHING

Elev.: K.B. 1165'  
 D.F. 1164'  
 G.L. 1160'

Date	5-29-67			
Run No.	ONE			
Depth-Driller	3620'			
Depth-Welex	3618'			
Btm. Log Inter.	3613'			
Top Log Inter.	202'			
Casing-Driller	8-5/8" @ 208'	@	@	@
Casing-Welex	202'			
Bit Size	7-7/8"			
Type Fluid in Hole	W. B. MUD			
Dens.   Visc.	10.3   162			
pH   Fluid Loss	9.5   11.6 ml	ml	ml	ml
Source of Sample	CIRCULATED			
R <sub>mf</sub> @ Meas. Temp.	0.90 @ 85°F	@ °F	@ °F	@ °F
R <sub>mf</sub> @ Meas. Temp.	0.60 @ 85°F	@ °F	@ °F	@ °F
R <sub>mc</sub> @ Meas. Temp.	1.10 @ 85°F	@ °F	@ °F	@ °F
Source R <sub>mf</sub> R <sub>mc</sub>	MEAS.   MEAS.			
R <sub>mf</sub> @ BHT	0.70 @ 104°F	@ °F	@ °F	@ °F
Time Since Circ.	3 HRS.			
Max. Rec. Temp.	104°F @ 3613'	°F @	°F @	°F @
Equip.   Location	7823   1STW.			
Recorded By	BURGESS			
Witnessed By	D. SOPER			

STATE RECEIVED  
 CORPORATION COMMISSION  
 JAN 4 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas