

We also need a well log on this well

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-091-20026-0000
WELL PLUGGING RECORD

Johnson County. Sec. 11 Twp. 14 Rge. 22E (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW

Lease Owner Fred Spindle

Lease Name Wenger Well No. 4

Office Address 1034 E. Peoria, Paola, Kansas 66071

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed KKK November 25, 1968 19 68

Application for plugging filed 12/2/68 19

Application for plugging approved 11/25/68 19

Plugging commenced 11/25/68 19

Plugging completed 11/25/68 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well James McDaniel

Producing formation Depth to top Bottom Total Depth of Well 726' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Cable tool hole pulled surface. Run
5 sacks cement at 726 feet slim hole.
Bridge set at 163 feet run 10 sacks cement.
Bridge set at 31 feet run 3 sacks cement.
Filled to surface with dirt.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Fred Spindle
Address 1034 E. Peoria, Paola, Kansas 66071

STATE OF Kansas COUNTY OF Miami, ss.
Fred Spindle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]

SUBSCRIBED AND SWORN to before me this 27th day of June, 19 69
[Signature] (Address)
My commission expires Oct. 16-1970
Notary Public.



R

Fred Spindle Drilling Contractor

Oil and Gas Well Repair

Log of Wenger No. 4 dry hole

1034 E. PEORIA
PAOLA, KANSAS
PH. AXTEL 4-3552

5	soil & clay	5
11	sanddy	16
15	lime	31
7	shale water	38
10	lime	48
8	shale	56
16	lime	72
21	shale water	93
70	lime	163
34	shale	197
8	lime	205
21	shale	226
6	lime	232
6	shale	238
6	lime	244
32	shale	276
2	lime	278
11	shale	289
27	lime	316
5	shale	321
24	lime	345
3	shale	348
3	lime	351
6	shale	357
8	lime	365
41	shale	416
9	sand dry	425
153	shale	578
4	lime	582
3	slate	585
5	shale	590
11	lime	601
6	shale	607
5	red bed	612
6	shale	618
11	shale	629
4	lime	633
52	shale	685
2	lime	687
18	shale	706
4	sand oil	710
6	sand broken oil	716
10	shale	726

hole plugged NOV. 1968

set 5 sacks cement in bottom
filled to 163 set 10 sacks cement
filled to 31 set 3 sacks of cement
filled to surface

T. D.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1969
CONSERVATION DIVISION
Wichita, Kansas