

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20688-00-01
Spot: SWSW Sec/Twnshp/Rge: 16-24S-16W
699 feet from S Section Line, 4523 feet from E Section Line
Lease Name: RUDD ESTATE A Well #: 4-16
County: EDWARDS Total Vertical Depth: 4455 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4358		
SURF	8.625	252		WITH 175 SX CMT
PROD	4.5	4447	0	WITH 175 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/23/2011 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: FG HOLL Phone: (620) 793-0915

Proposed Plugging Method: RUN TBG TO 4309' & PUMP 200# HULLS & 30 SX CMT. PULL TBG & PERFORATE @ 1130'. RUN TBG TO 4309' & CIRCULATE CMT UP BOTH SIDE OF THE PRODUCTION CASING. PULL TBG & TOP WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2011 2:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

****WELL HAS A SHALLOW CASING LEAK**** BOTTOM PLUG CIRCULATED MUD THEN PUMPED 150# HULLS & 30 SX CMT AT 4309'. PULLED TBG & PERFORATED AT 1130'. RAN TBG TO 1130' & CIRCULATED CMT UP BOTH SIDES OF PRODUCTION CASING WITH 360 SX CMT. PULLED TBG & TOPPED OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4309	4316		CONGLOMERATE

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
SEP 29 2011
KCC DODGE CITY

Form CH 2/3
10/12/11