

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22418-00-00
Spot: NWENWSW Sec/Twnshp/Rge: 7-18S-21W
2343 feet from S Section Line, 4571 feet from E Section Line
Lease Name: ROTH Well #: 2-B
County: NESS Total Vertical Depth: 4305 feet

Operator License No.: 32158
Op Name: H & B PETROLEUM CORP.
Address: PO BOX 277
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	519		WITH 325 SX CMT
DVT		1491		
PROD	4.5	4305		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2011 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: AL HAMMERSMITH Company: H & B PETROLEUM Phone: (620) 564-3002

Proposed Plugging Method: RUN TBG TO BOTTOM OF HOLE & FILL WITH CMT TO SURFACE. PRESSURE TEST 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2011 2:35 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 4075'. PUMPED 100# HULLS & 60 SX CMT. PULLED TBG TO 2696'. PUMPED 60 SX CMT. GOOD CIRCULATION. PULLED TBG TO 1504'. PUMPED 94 SX CMT. CIRCULATED CMT TO SURFACE. PULLED TBG OUT OF HOLE & TOPPED OFF 4 1/2" WITH 11 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 1800 PSIG WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4201	4206		FORT SCOTT

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
SEP 29 2011
KCC DODGE CITY

Form CP-2/3
10/12/11