

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00947-00-01
Spot: NENW Sec/Twnshp/Rge: 13-2S-19W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: HUFFSTUTTER Well #: 1W1
County: PHILLIPS Total Vertical Depth: 3737 feet

Operator License No.: 3182
Op Name: NPF ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	234	0	200 SX
PROD	5.5	3734	0	125 SX

Well Type: EOR UIC Docket No: E08141.4 Date/Time to Plug: 10/03/2011 9:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: PAT H COCHRAN Company: BACH, JASON DBA BACH OIL PRO Phone: (714) 730-7850

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel spacer.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2011 12:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3291' - pumped 8 sxs gel spacer - followed with 75 sxs 60/40 pozmix - 4% gel - 200# hulls.
Pulled tubing to 1750' - pumped 225 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 30 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus - pumped 15 sxs 60/40 pozmix - 4% gel.
No pressure. Leaking out of Braden head.

Perfs:

Top	Bot	Thru	Comments
3322	3500		LKC

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS SKELTON #1. COPELAND ACID AND CEMENTING COMPANY-TICKET #37358.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

OCT 06 2011

Form CP-2/3

cc to UIC 10/12/11
10/12/11