

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22998-00-00
Spot: SENESWNW Sec/Twnshp/Rge: 8-30S-11W
1900 feet from N Section Line, 1100 feet from W Section Line
Lease Name: BARBARA Well #: 1-8
County: BARBER Total Vertical Depth: 3859 feet

Operator License No.: 32192
Op Name: PRIDE ENERGY COMPANY, A GENERA
Address: P O BOX 701950
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2700		WITH 2 SX CMT
CIBP		3050		
CIBP		3170		
SURF	8.625	318		WITH 250 SX CMT
DVT		2492		310 SX CMT.
PROD	5.5	3368	727	WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/27/2011 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 2700' WITH 2 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 09/27/2011 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2700' WITH 2 SX CMT. 1ST PLUG RIHWT TO 703'. MIX & PUMP 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 350'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3190	3198		TOPEKA
3065	3070		TARKIO
2758	2786		INDIAN CAVE

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED

SEP 30 2011

KCC DODGE CITY

Signed

Richard M. Lacey

(TECHNICIAN)

Form CP-2/3

10/12/11