

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20747-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 31-29S-11W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: COSS A Well #: 1  
County: PRATT Total Vertical Depth: 2855 feet

Operator License No.: 32192  
Op Name: PRIDE ENERGY COMPANY, A GENERA  
Address: P O BOX 701950  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2570		WITH 2 SX CMT
SURF	8.625	447		
PROD	4.5	2851	1235	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/16/2011 4:30 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 09/16/2011 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*PBT 2851\*\* CIBP @ 2570' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2748	2788		INDIAN COVE
2622	2630		RED EAGLE

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
SEP 30 2011  
KCC DODGE CITY

RECEIVED  
OCT 11 2011  
KCC WICHITA

Form CP-211  
10/12/11