

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20531-00-00  
Spot: E2SWSE Sec/Twnshp/Rge: 26-34S-30W  
596 feet from S Section Line, 1570 feet from E Section Line  
Lease Name: ADAMS Well #: 2-26  
County: MEADE Total Vertical Depth: 6100 feet

Operator License No.: 5225  
Op Name: QUINQUE OPERATING COMPANY  
Address: 908 NW 71ST ST  
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5900		WITH 10 SX CMT
SURF	8.625	1498		WITH 725 SX CMT
PROD	4.5	6098	1750	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2011 9:30 AM  
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.  
Proposal Rcvd. from: BLAINE FLAIMING Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 202-0046

Proposed Plugging Method: PUMP 40 BBLS MUD DOWN 4-1/2 CSG. SET CIBP AT 5900'. PUMP 10 SX CMT ON TOP. SHOOT CSG AT FREE POINT. LAY DOWN SAME. TIH WITH TBG. LOAD HOLE WITH MUD AND PUMP 300# COTTON SEED HULLS. PUMP 50 SX CMT AT 1525'. TOH TO 600'. PUMP 60 SX CMT. TOH TO 60'. PUMP CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/27/2011 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5900' WITH 10 SX CMT. TIH WITH TBG. LOAD HOLE WITH MUD & PUMP 300# HULLS. 1ST PLUG AT 1522' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5949	5957		

Remarks: USED COMMON CEMENT BY PHIL DOLLARD OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed Kenny M. Sullivan  
(TECHNICIAN)

RECEIVED

SEP 30 2011

KCC DODGE CITY

RECEIVED  
OCT 11 2011  
KCC WICHITA

Form (P) 28  
10/12/11