

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20661-00-00
Spot: W2NW Sec/Twnshp/Rge: 29-34S-30W
1320 feet from N Section Line, 660 feet from W Section Line
Lease Name: HOLMES Well #: 1-29
County: MEADE Total Vertical Depth: 6350 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4290		WITH 10 SX CMT
SURF	8.625	1460		WITH 500 SX CMT
PROD	4.5	4875	1725	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/20/2011 9:30 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: PEDRO Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 202-0046

Proposed Plugging Method: PUMP 40 BBLS MUD DOWN 4-1/2 CSG. SET CIBP AT 4300'. PUMP 10 SX CMT ON TOP. SHOOT CSG AT FREE POINT. LAY DOWN SAME. TIH WITH TBG. LOAD HOLE WITH MUD AND PUMP 300# COTTON SEED HULLS. PUMP 50 SX CMT AT 1490'. TOH TO 600'. PUMP 50 SX CMT. TOH TO 60'. PUMP CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2011 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4290' WITH 10 SX CMT. CIRCULATE HOLE WITH MUD & HULLS THROUGH TBG. 1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 602' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 25 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4476	4480		
4348	4352		
4340	4344		

RECEIVED
OCT 11 2011
KCC WICHITA

Remarks: USED COMMON CEMENT BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
SEP 30 2011

KCC DODGE CITY

Form CP-2/0

10/11/11