

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22384-00-00
Spot: SESENE SW Sec/Twnshp/Rge: 1-20S-7W
1443 feet from S Section Line, 2690 feet from E Section Line
Lease Name: KIMBALL Well #: 1
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	243		160 SX CMT
PROD	5.5	3350	2400	100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2011 1:00 PM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed
Plugging
Method:

SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2011 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OH TO 3280' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 2400' AND PULL TO 1025' AND PUMP 35 SX'S COMMON CEMENT. PULL CASING TO 600'. LET SET FOR APPROX. 1 HR--TAG AT 750'. PUMP 35 SX'S COMMON CEMENT AT 600'. PULL CASING TO 290' AND CIRCULATE 60-40 4% GEL CEMENT, TO SURFACE. PULL OUT CASING AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3350	3360	OH	

RECEIVED

OCT 12 2011

KCC WICHITA

Remarks: COPELAND TICKET C-37265

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

10/17/11

JK