

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21935-00-00  
Spot: E2SWSENW Sec/Twnshp/Rge: 27-28S-8W  
2310 feet from N Section Line, 1900 feet from W Section Line  
Lease Name: YOUNG Well #: 3  
County: KINGMAN Total Vertical Depth: 4210 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	285		
T1	2.375	4138		
PROD	4.5	4214	2840	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2011 12:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMIE HARRIS Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/27/2011 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4030' CAPPED WITH 43 SX OF CEMENT. CUT PIPE OFF AT 2840', PULLED CASING TO 1300' SPOTTED 35 SX OF CEMENT. PULLED CASING TO 800' SPOTTED 35 SX OF CEMENT, PULLED CASING TO 335' CIRCULATED TO SURFACE WITH 135 SX OF CEMENT ON 6/23/11. 6/27/11 TOP PLUG FELL BACK 140', RAISED TO SURFACE WITH 15 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4109	4112		

RECEIVED  
OCT 12 2011  
KCC WICHITA

Remarks: DENITED TA - COPELAND CEMENT OUT OF GREAT BEND - TICKET 336764

Plugged through: CSG

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)

10/17/11

JK