

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21398-00-01)
Spot: NWNE Sec/Twnshp/Rge: 23-30S-7W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HUFFORD Well #: 7
County: KINGMAN Total Vertical Depth: 4286 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		200 SX
T1	2.875	4091		
PKR		4091		
PROD	5.5	4284	2020	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2011 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (580) 237-6152

Proposed Plugging Method: SAND TO 4100' & 5 SKS, REC CASING, 35 SX 1250' 35 SX 700', CIRC CMT 300-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/03/2011 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TUBING STUCK IN HOLE. SHOT OFF TUBING AT 3800'. WOOD PLUG TO TOP OF FISH 50' SAND & 5 SKS CMT. REC CASING FROM 2020'. SPOTTED 35 SXS 1250', PULLED CASING TO 700' SPOTTED 35 SXS CMT. PULLED CASING TO 300' & CIRCD CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4195	4205	CSG	
4170	4194	CSG	

Remarks: QUALITY WELL SERVICE 60/40.4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
OCT 12 2011
KCC WICHITA