

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20380-00-00
Spot: N2NESE Sec/Twnshp/Rge: 4-22S-2W
2310 feet from S Section Line, 660 feet from E Section Line
Lease Name: SCHRAG Well #: B-3
County: HARVEY Total Vertical Depth: 3300 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		
PROD	4.5	3300	700	

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/23/2011 12:00 AM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/26/2011 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SANDED BOTTOM TO 3140' CAPPED WITH 4 SX CEMENT ON 5/24/11. 5/25/11 CUT PIPE OFF AT 700' PULLED TO 400' SET 160 SX HOT PLUG WITH 3% CC & 150 LBS OF COTTONSEED HULLS. 5/26/11 CEMENT TAGGED AT 190'-RAN IN WITH POLY PIPE AND TOPPED OFF WITH 90 SX OF CEMENT.

Remarks: COPELAND CEMENT CO. OUT OF BURRTON-TICKET NUMBER 37687--TEN YEAR RULE

Plugged through: CSG

RECEIVED
OCT 12 2011
KCC WICHITA

District: 02

Signed B. J. Hope
(TECHNICIAN)

Form CP-2/3

10/17/11