

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21144-00-01
Spot: SWNENWNE Sec/Twnshp/Rge: 22-20S-10W
4904 feet from S Section Line, 1673 feet from E Section Line
Lease Name: MADDEN Well #: 1
County: RICE Total Vertical Depth: 3493 feet

Operator License No.: 34360
Op Name: EC SERVICES, LLC
Address: PO BOX 543
BENTON, KS 67017

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	3.5	3943		FIBERGLASS
SURF	8.625	260		250 SX
T1	3.5	3493		160 sxs

Well Type: SWD UIC Docket No: D20978.0 Date/Time to Plug: 10/03/2011 2:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: Phone: (620) 960-1288

Proposed Plugging Method: ACCORDING TO THE RULES AND REGULATIONS OF THE KCC.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2011 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, RUN 1.5" TUBING TO 3000' AND PUMP 25 SX'S COMMON CEMENT. PULL TUBING OUT AND LET CEMENT SET OVERNIGHT--TAG NEXT MORNING AT 2367'. PERFORATE AT 1300', RUN TUBING TO 1300' AND PUMP 35 SX'S COMMON CEMENT. LET SET--TAG AT 1200'. PERFORATE AT 900'. RUN TUBING BACK INTO 900' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING OUT AND PERORATE AT 310'. RUN TUBING BACK DOWN TO 310' AND CIRCULATE 130 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED APPROX. 260 SX'S CEMENT.

~~* FAILED MIT WHEN OPERATED BY KEY GAS.~~

Perfs:

Top	Bot	Thru	Comments
3419	3493	TBG	

RECEIVED
OCT 12 2011

Remarks: COPELAND TICKET C-37793. GRESSELL PERF TICKET 0833.

Plugged through: TBG

KCC WICHITA

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

Form CP-2/3

cc to MIC 10/13/11