

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21088-00-00  
Spot: NENW Sec/Twnshp/Rge: 2-21S-6W  
660 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: WALSTEN Well #: A 1  
County: RICE Total Vertical Depth: 3401 feet

Operator License No.: 30525  
Op Name: LANGSTON, D. S.  
Address: 310 W CENTRAL STE 202  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	282		235 SX
PROD	5.5	3386	2211	75 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2011 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: \_\_\_\_\_ Phone: (620) 562-0895

Proposed Plugging Method: PER KCC INSTRUCTIONS.

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE  
Date/Time Plugging Completed: 10/06/2011 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3335' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 2211' AND PULL TO 900' AND PUMP 35 SX'S CEMENT WITH 2% CC. PULL CASING ON UP TO 500'. LET SET AWHILE AND TAG CEMENT WITH WIRELINE AT 842'. PUMP 35 SX'S AT 500'. PULL CASING ON UP TO 340' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED 190 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3386	3401	OH	

Remarks: 60-40 POZ. 4% GEL. COPELAND TICKET C-39605

Plugged through: CSG

RECEIVED  
OCT 12 2011

KCC WICHITA

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

Form CP-2/3

10/17/11

JK