

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22020-00-00
Spot: NESW Sec/Twnshp/Rge: 27-20S-21W
2005 feet from S Section Line, 1989 feet from W Section Line
Lease Name: HINNERGARDT Well #: 1-27
County: NESS Total Vertical Depth: 4465 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	458		WITH 325 SX CMT
PC		1408		
PROD	5.5	4463	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2011 8:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: SET CIBP @ 4350' WITH 2 SX CMT. LOAD HOLE WITH WATER & RUN BOND LOG. IF NO CMT SPOT 40 SX PLUG AT 1500' THEN PERFORATE AT 700'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2011 7:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN BOND LOG & FOUND TOP OF CMT AT 450'. COULDN'T GET CIBP TO BOTTOM. RAN TBG TO 3510' & PUMPED 35 SX CMT & 100# HULLS. PULLED TBG TO 1500' & PUMPED 165 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4398	4410		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
OCT 14 2011
KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
OCT 11 2011
KCC DODGE CITY

Form CP 23
10/17/11