

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10230-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 25-34S-30W
4553 feet from S Section Line, 4610 feet from E Section Line
Lease Name: ADAMS D Well #: 3
County: MEADE Total Vertical Depth: 5381 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5300		WITH 10 SX CMT
SURF	13.375	635		WITH 500 SX CMT
	11 9.625	2723		WITH 800 SX CMT
PROD	5.5	5458	2780	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2011 9:30 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: BLAINE FLAMING Company: PHIL DOLLAR OILFIELD Phone: (806) 202-0046

Proposed Plugging Method: PUMP 40 BBLC MUD DOWN 5-1/2 CSG. SET CIBP AT 5300'. PUMP 10 SXS CMT ON TOP. SHOOT CSG AT FREE POINT. LAY DOWN SAME. TIH WITH TBG. LOAD HOLE WITH MUD AND PUMP 300# COTTON SEED HULLS. PUMP 50 SX CMT AT 2723'. TOH TO 600'. PUMP 25 SXS CMT. TOH TO 60'. PUMP CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2011 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

PUMP 40 BBLS MUD DOWN 5 1/2" CASING. SET CIBP @ 5300' & PUMP 10 SX CMT ON TOP. TIH WITH TBG. LOAD HOLE WITH MUD & PUMP 300# HULLS. 1ST PLUG AT 2750' WITH 50 SX CMT. 2ND PLUG AT 1470' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 50 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5368	5372		

Remarks: USED CLASS H CMT BY PHIL DOLLARD OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED
OCT 11 2011
KCC DODGE CITY

Signed

Kenny M. Sullivan
(TECHNICIAN)

RECEIVED
OCT 14 2011
KCC WICHITA

Form CP-23
10/17/11