

1080246

TO: STATE CORPORATION COMMISSION

6-2

API NUMBER 15-071-20,235-00-60  
NW NW NW SEC. 23, T 17 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KLEWENO WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 97.34

OPERATOR LICENSE # 32199

WELL TOTAL DEPTH 2995 FEET

OPERATOR: FLEX SYSTEMS

PRODUCTION CSG: SIZE 4 1/2" @ 2995' WITH 300SX

NAME AND PO BOX 730

SURFACE CASING: SIZE 8 5/8" @ 278' WITH 275SX

ADDRESS FORNEY, TX 75126

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 02 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DAVE OLSON

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2951-59

1ST PLUG ALLIED PUMPED DOWN 4 1/2" CASING 300# HULLS & 25 SX CEMENT. PRESSURED UP TO 300#.

USED 60/40 POZMIX 6% GEL WITH 3% CC.

2ND PLUG PEAK WIRE LINE SERVICE PERFORATED AT 1500'. ALLIED PUMPED DOWN 4 1/2" CASING 80 SX

CEMENT, 100# HULLS, 90 SX CEMENT. SHUT IN AT 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 50 SX

CEMENT. SHUT IN AT 100#. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:40 AM DAY: 02 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG ALLIED PUMPED DOWN 4 1/2" CASING 300# HULLS AND 25 SX CEMENT. PRESSURED UP TO 300#.

USED 60/40 POZMIX 6% GEL WITH 3% CC.

2ND PLUG PEAK WIRE LINE SERVICE PERFORATED AT 1500'. ALLIED PUMPED DOWN 4 1/2" CASING 80 SX

CEMENT, 100# HULLS, AND 90 SX CEMENT. SHUT IN WITH 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS

50 SX CEMENT. SHUT IN WITH 100#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

INVOICED

RECEIVED

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

DATE 6-9-99

INV. NO. 61015

JUN 04 1999

06-04-99 SIGNED  
CONSERVATION DIVISION  
Wichita, Kansas

Kevin D. Strube  
(TECHNICIAN)

FORM CP-2/3