

1 110071

8-19-87

API NUMBER 15- 071-20,442-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SE, SEC. 36, T 17 S, R 43 W/E

TECHNICIAN'S PLUGGING REPORT

330 feet from S section line

330 feet from E section line

Operator License # 5804

Lease Name Lang Well # 36-1

Operator: Dreiling Ltd. of Colorado

County Greeley 172.41

Name & Address 410 17th Street, Suite 1140

Well Total Depth 5305 feet

Denver, CO 80202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor R & C Drilling Company, Inc. License Number 9087

Address Box 296, Hays, KS 67601

Company to plug at: Hour: 6:30 a.m. Day: 19 Month: 8 Year: 19 87

Plugging proposal received from Larry Folker

(company name) R & C Drilling Company, Inc. (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2652-79'

1st plug at 2660' with 50 sx cement, 2nd plug at 1640' with 80 sx cement,

3rd plug at 450' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:45 a.m. Day: 19 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2660' with 50 sx cement,

2nd plug at 1640' with 80 sx cement,

3rd plug at 450' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

AUG 20 1987

08-20-87

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED  
I will observe this plugging.

DATE 8-24-87

Signed James R. Kray (TECHNICIAN)

INV. NO. 17934

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date August 5, 1987 month day year 1987

API Number 15-071-20442-0000

OPERATOR: License # 5804 Name Dreiling, Ltd. of Colorado Address 410. 17th St., #1140 City/State/Zip Denver, CO 80202 Contact Person Les Olson Phone (303) 623-6144

SE SE SE Sec 36 Twp 17 S, Rg 43 East West 330 Ft. from South Line of Section 330 Ft. from East Line of Section

CONTRACTOR: License # 9087 Name R. E. C. Drilling Co., Inc. City/State Box 296, Hays, Kansas 67601

(Note: Locate well on Section Plat on reverse side)

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet County Greeley Lease Name Lang Well # 36-1 Ground surface elevation feet MSL Domestic well within 350 feet yes no Municipal well within one mile yes no Depth to bottom of fresh water 100 Depth to bottom of usable water 1400 Surface pipe by Alternate 1 2 Surface pipe planned to be set 400 Conductor pipe required Projected Total Depth 5400 Formation Mississippian

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 8/3/87 Signature of Operator or Agent Title

For KCC Use: Conductor Pipe Required 300 feet Minimum Surface Pipe Required 300 feet per Alt. 1 2 This Authorization Expires 2-3-88 Approved By 8-3-87

Work in 8-6-87 set 400' of 8 5/8

SE SE SE Sec 36 Twp 17 S, Rg 43 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ TD feet depth with 25 Cement 25 of 60/40 POZ. 6% Gel
2nd plug @ Anhydrite feet depth with 20 60/40 POZ. 6% Gel
3rd plug @ Dakota feet depth with 100 60/40 POZ. 6% Gel
4th plug @ Surface 50 feet depth with 40 60/40 Poz. 6% Gel
5th plug @ 40 feet depth with 10 60/40 Poz. 6% Gel
(2) Rathole with 15 (b) Mousehole with

Mousehole 10

PUSHER Rick Finnsa TD 5300 FORMATION SURFACE PIPE 8 5/8 @ 425 ANHYDRITE 2657 ELEVATION 3899 105 STARTING TIME & DATE COMPLETION TIME & DATE 1st PLUG @ 2660 FT. W/ 50 SX SX 2nd PLUG @ 1640 FT. W/ 80 SX SX 3rd PLUG @ 450 FT. W/ 50 SX SX 4th PLUG @ 40-0 FT. W/ 10 SX SX RAT HOLE CIRCULATED W/ 15 SX SX MOUSE HOLE CIRCULATED W/ SX SX WATER WELL PLUGGED W/ Mucialur 6/4 702 607000 CEMENT COMPANY TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION AUG 20 1987 CONSERVATION DIVISION Wichita, Kansas