

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20769-00-00
Spot: NENENW Sec/Twnshp/Rge: 12-17S-43W
330 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: CROTINGER Well Number: 1-12
County: GREELEY Total Vertical Depth: 5172 feet

Operator License No.: 33011
Op Name: DEKA EXPLORATION, INC.
Address: PO BOX 14057
OKLAHOMA CITY, OK 73113

Surface Casing Size: 8.625 feet: 268

\$168⁰⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/26/2003 7:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: DAVID CUNNINGHAM Company: DEKA EXPLORATION Phone: (405) 749-0004

Proposed Plugging Method: 1ST PLUG AT 2669' WITH 50 SX CMT. 2ND PLUG AT 1950' WITH 80 SX CMT. 3RD PLUG AT 950' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/26/2003 10:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 2690' WITH 50 SX CMT. 2ND PLUG AT 1966' WITH 80 SX CMT. 3RD PLUG AT 964' WITH 50 SX CMT. 4TH PLUG AT 311' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
SEP 15 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
AUG 28 2003
KCC Dodge City

Signed

Stephen J. Porter
(TECHNICIAN)

INVOICED

DATE 9-15-03

INV. NO. 2004060502

Form CP-2
[Signature]