

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20239-00-01  
Spot: CW2SW Sec/Twnshp/Rge: 32-19S-39W  
660 feet from S Section Line, 330 feet from W Section Line  
Lease/Unit Name: JONES Well Number: 1  
County: GREELEY Total Vertical Depth: 2870 feet

Operator License No.: 7271  
Op Name: BARTLING OIL COMPANY  
Address: 1001 CANYON EDGE DR.  
AUSTIN, TX 78733

Conductor Pipe: Size feet: 93.28  
Surface Casing: Size 8.625 feet: 289 WITH 225 SX CMT  
Production: Size 4.5 feet: 2866 WITH 400 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/15/2002 9:05 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WARREN OSCHNER Company: BARTLING OIL Phone: (512) 795-9593

Proposed Plugging Method: SET CIBP @ 2766' WITH 2 SX CMT. LOAD CASING & TEST. RUN BOND LOG. FIND TOC. SHOOT @ 1400'.  
CIRCULATE CMT TO SURFACE OR TOC OF SURFACE.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/15/2002 12:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 2863'. PERFS AT 2816-26'. SET CIBP @ 2766' WITH 2 SX CMT SPOTTED ON TOP BY DUMP BAILER. LOADED HOLE. RAN BOND LOG. TOC @ 70'. PERFORATED AT 1306'. PUMP 300# HULLS & 165 SX CMT. PRESSURED UP TO 500# & HELD. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 5 SX CMT. PRESSURED UP TO 500# & SHUT IN.

RECEIVED  
NOV 20 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Kevin D. Strube  
(TECHNICIAN)

INVOICED

DATE 11-21-02  
INV. NO. 2003060850

