

1080234

TO: STATE CORPORATION COMMISSION

12-15

API NUMBER 15-071-20,657-00-00
W/2 NE SEC. 30, T 19 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MEC REXFORD WELL # 1-30

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 92, 63

OPERATOR LICENSE # 5263

WELL TOTAL DEPTH 2850 FEET

OPERATOR: MIDWESTERN EXPLORATION CO. PRODUCTION CSG: SIZE 4 1/2" @ 2832' WITH 625 SX

NAME AND PO BOX 1884 SURFACE CASING: SIZE 8 5/8" @ 252' WITH 175 SX

ADDRESS LIBERAL, KS 67905-1884

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 9:20 AM DAY: 15 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 2838' - 50'

DUMP 500 SX HULLS AHEAD OF 175 SX CEMENT TO FILL CASING TO SURFACE. PUT 50 SX CEMENT

DOWN 8 5/8" X 4 1/2" ANNULUS IF POSSIBLE. CUT CASING OFF 4' BELOW SURFACE AND WELD CAP ON WELL.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 15 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT 12-18-98

ALLIED CEMENTING PUMPED DOWN 4 1/2" 200# HULLS WITH 100# HULLS MIXED IN FIRST PART OF CEMENT

PUMPED 140 SX CEMENT. MAXIMUM PSI PRESSURE AT 500#. SHUT IN AT 500#. PRESSURED UP

4 1/2 X 8 5/8 ANNULAS TO 500#. SHUT IN AT 500#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Strube (TECHNICIAN) FORM CP-2/3

DEC 29 1998

60493

12-15 AUG 27 1999