

1 020014

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,416-00-00  
SW SW SW SEC. 19, T 19 S, R 39 W 23  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4728

Lease Name Abbott Well # 1

Operator: Earth Minerals Search, Inc.  
Name & Address P. O. Box 441023  
Houston, TX 77244

County Greeley 96.01  
Well Total Depth 2954 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Earth Minerals Search, Inc. License Number 4728

Address P. O. Box 441023, Houston, TX 77244

Company to plug at: Hour: 11:40 am Day: 31 Month: March Year: 19 86

Plugging proposal received from Clint Ashley

(company name) Earth Minerals (phone) 303-336-7139

were: 4 1/2" at 2954' PBD 2954' Perfs at 3847-2861

Pump 2 sx hulls, with gel, 140 sx cement with 3% cc 6% gel

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 p Day: 31 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Pumped 2 sx hulls with 40 sx cement filled with 12 sx gel,  
90 sx cement, filled pipe. Stopped pumping with 1500 psi. Pipe standing full. Cut off  
4' below ground level and welded cap on.

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1986

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: No recovery. Cemented by Halliburton. Used 60/40 Pozmix 3% cc 6% gel  
(If additional description is necessary, use BACK of this form.)

INVOICED

APR 15 1986

DATE \_\_\_\_\_

INV. NO. 13405

3-31

Signed Glenn R. Barlow  
(TECHNICIAN)