

8-26

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-071-20,527-00-00
C SE, SEC. 16, T 19 S, R 39 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5263
Operator: Midwestern Exploration Co.
Name & Address 111 E. 11th.
Liberal, KS 67901

Lease Name Sage - Taylor Roelf Well # 1-16
AMB VCC
County Greeley 104.65
Well Total Depth 3220 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 s.m. Day: 25 Month: 8 Year: 19 95

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Work: 4 1/2" at 3219' w/550 sx cement, PBTD 3216', Perfs at 2850-56',
1st plug pump 1 sx hulls and 20 sx cement at 2750',
2nd plug pump 20 sx cement at 1400',
3rd plug pump 20 sx cement at 700', 4th plug pump 20, sx cement at 300',
5th plug pump 10 sx cement at 40', 6th plug pump 80 sx cement down 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12 p.m. Day: 26 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at 2850-2650'
2nd plug pumped 20 sx cement at 1400-1200',
3rd plug pumped 20 sx cement at 700-500',
4th plug pumped 20 sx cement at 300-100',
5th plug pumped 5 sx cement at 40-0',
6th plug pumped 30 sx cement down 4 1/2" X 8 5/8" annulus. Shut in pressure 500 psi.

RECORDED
STATE CORPORATION COMMISSION
AUG 29 1995
08-29-95
WICHITA, KANSAS

Remarks: Used common cement by Sargent & Horton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

(check & if not) observe this plugging.

DATE 9-6-95

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 43412