


15-071-20017-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Greeley County, Sec. 23 Twp. 17S Rge. 40W (E) (W)
Location as "NE/CNW&SW" or footage from lines C SE
Lease Owner Dorchester Exploration, Inc.
Lease Name Wear #1 Well No. 1
Office Address 1201 Vaughn Building, Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 22, 1973 19
Application for plugging filed January 20, 1973 19
Application for plugging approved January 20, 1973 19
Plugging commenced 10:00 PM, January 21, 1973 19
Plugging completed 12:00 Midnight - January 21, 1973 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3006' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	377'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Pumper 140 cu. ft. through open end
D.P. at 1350', 40 cu. ft. at 400' -
20' at 40' to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1973
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and sworn to before me this 26th day of January, 1973.
Bernard Laudermilk
Bernard Laudermilk, Notary Public.



My commission expires _____
BERNARD LAUDERMILK - NOTARY PUBLIC
My Commission Expires Jan. 22, 1974

15-071-20017-00-00

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- BAR #1
Located: C SE, Section 23-17E-40N, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 16, 1973
COMPLETED: January 22, 1973

TOTAL DEPTH: 3006'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 190 Shale and Gravel	Ran 8 joints 10 3/4", 8rd, Rge. 13, new casing, 368.51' set at 377' K.B. with 150 sacks Howco Light with 2% cc, followed with 150 sacks Common with 3% cc. Plug down 8:15 AM, 1-17-73.
190 - 1064 Shale	
1064 - 1660 Shale and Sand	
1660 - 1842 Shale, Sand and Lime	
1842 - 2325 Shale and Lime	
2325 - 2610 Shale and Anhy. Stringers	
2610 - 2695 Lime and Shale - Sand	
2695 - 2882 Lime and Shale	
2882 - 2970 Shale and Lime and Anhy.	
2970 - 3006 Lime and Shape	Plugged.

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1973
CONSERVATION DIVISION
Topeka, Kansas

15-071-20017-00-00

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- EAR #1
Located: T. 1N, Section 23-17E-40, Creole County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 16, 1973
COMPLETED: January 22, 1973

TOTAL DEPTH: 3006'

<u>LOG</u>	<u>CONTINUED FROM</u>
0 - 190 Shale and Gravel	Run 8 joints 10 3/4", Ard, Rge. '3, new casing, 368.51' set at 377' A.B. with 150 sacks Maxco Light with 2% cc, followed with 150 sacks Common with 3% cc. Plug down 7:15 AM, 1-17-73.
190 - 1064 Shale	
1064 - 1660 Shale and Sand	
1660 - 1842 Shale, Sand and Lime	
1842 - 2325 Shale and Lime	
2325 - 2610 Shale and Anhy. stringers	
2610 - 2695 Lime and shale - sand	
2695 - 2882 Lime and shale	
2882 - 2970 Shale and Lime and Anhy.	
2970 - 3006 Lime and Shale	lugged.