

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-206980000

LEASE NAME Diane

WELL NUMBER 1

NOV 22 1999  
11-22-99

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1320 <sup>FNL</sup> Ft. from 5 Section Line

1320 Ft. from E Section Line

SEC. 22 TWP. 17 RGE. 40 (E) (W)

CONSERVATION DIVISION  
Wichita, Kansas

LEASE OPERATOR Horseshoe Operating, Inc.

COUNTY Greeley

ADDRESS 500 W. Texas, Suite 1190

Date Well Completed 12/18/98

PHONE (915) 683-1448 OPERATORS LICENSE NO. 4894

Plugging Commenced 10/25/99

Character of Well Gas

Plugging Completed 10/25/99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/24/99 (date)

by David P. Williams w/ KCC (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3014'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Ft. Riley	Gas - Saltwater	232	0	8-5/8	232	0
2964-2991		3014	0	4-1/2	3014	0
Dakota	Water					
1100-1200'						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

Pump 400# hulls, 185 sacks 60/40 Poz 6% gel cement down 4-1/2" casing.  
Max pressure 600#. Shut-in pressure 600#. Hooked up to backside. Pump  
30 sacks, 60/40 POZ cement down backside, pressure-up to 300#. RD.

Name of Plugging Contractor Swift Services License No. \_\_\_\_\_

Address P. O. Box 466 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Horseshoe Operating, Inc.

STATE OF Texas COUNTY OF Midland, ss.


Jim Dixon (Employee of Operator) or (Operator) c above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 500 W. Texas, Suite 1190

SUBSCRIBED AND SWORN TO before me this 19 day of November, 19 99

Debbie Franklin  
Notary Public



Commission Expires: 8-9-2001